# Awaken® B90



24" four-function handshower kit, 2.5 gpm

## K-98362-Y

#### **Features**


- Advanced spray engine provides three alternate experiences: wide coverage, intense drenching, and targeted spray
- Wide coverage spray produces an encompassing spray for everyday use
- Intense drenching spray delivers a forceful spray ideal for rinsing shampoo from hair
- Targeted spray is a focused stream for targeting sore muscles or use as a utility spray
- Pause feature temporarily pauses water flow to conserve water while you lather, shave, or shampoo
- Thumb tab allows for a smooth transition between sprays
- MasterClean™ sprayface features an easy-to-clean surface that withstands mineral buildup
- 2.5 gpm (9.5 lpm) maximum flow rate at 45 psi (3.1 bar)
- 24" (609 mm) slidebar features adjustable mounting brackets for installation flexibility
- 60" (1524 mm) hose length

## Material

- **Durable material construction**
- KOHLER finishes resist corrosion and tarnishing

### Installation

Wall-mount



## Codes/Standards

ASME A112.18.1/CSA B125.1 DOE - Energy Policy Act 1992

## **KOHLER® Faucet Lifetime Limited** Warranty

See website for detailed warranty information.


#### Available Colors/Finishes

Color tiles intended for reference only.

Color	Code	Description
	CP	Polished Chrome
	BN	Vibrant® Brushed Nickel



24" four-function handshower kit, 2.5 gpm K-98362-Y



#### **Technical Information**

All product dimensions are nominal.

Drain included:

No

Handshower:

Rated maximum 2.5 gal/min (9.5 l/min)

flow:

Pressure: 45 psi (3.1 bar)

### **Notes**

Install this product according to the installation instructions.

Plumbing codes require approved backflow prevention devices to be installed in-line to handshowers. Please consult with local plumbing officials.

Mount the slidebar to stud framing or install backing support. For tile or other solid finish surfaces: Predrill mounting holes through surface material only; do not drill into the stud. For drywall surface: No predrill is required.

NOTE: The mounting brackets can be adjusted to align with existing holes for retrofit installations.

